

SISTEMA SANCAD

18/12/2006 às 14:17h

Rede de Água - Seccionamentos - Dados Finais

Cidade : P. A. VALE VERDE - TURBILHÃO 1 E 2

Nu	No Jus	No Mo	Compr m	Q Jus l/s	Q mar l/s	Q Mon l/s	Q fict l/s	DN1 mm	DN2 mm	Vel m/s	Hf mca	CP Juz mca	CT Juz m	PR Juz mca	PR Est mca	Perda Km mca	Obs
1	1	0	52.00	1.73	0.02	1.75	1.74	75		0.37	0.12	456.799	442.930	13.869	15.440	2.330	
2	2	1	68.00	0.61	0.02	0.64	0.62	50		0.27	0.14	456.664	444.060	12.604	14.310	1.990	
3	3	2	188.00	0.05	0.07	0.11	0.08	50		0.03	0.01	456.653	443.240	13.413	15.130	0.060	
4	4	3	44.00	0.00	0.02	0.02	0.01	50		0.00	0.00	456.653	442.900	13.753	15.470	0.000	
5	5	3	92.00	0.00	0.03	0.03	0.02	50		0.01	0.00	456.653	443.160	13.493	15.210	0.000	
6	6	2	90.00	0.34	0.03	0.38	0.36	50		0.15	0.07	456.597	444.040	12.557	14.330	0.740	
7	7	6	187.00	0.04	0.07	0.10	0.07	50		0.03	0.01	456.589	443.160	13.429	15.210	0.040	
8	8	7	100.00	0.00	0.04	0.04	0.02	50		0.01	0.00	456.589	444.520	12.069	13.850	0.000	
9	9	6	92.00	0.11	0.03	0.15	0.13	50		0.06	0.01	456.585	441.260	15.325	17.110	0.130	
10	10	9	183.00	0.02	0.06	0.08	0.05	50		0.02	0.01	456.580	444.520	12.060	13.850	0.030	
11	11	10	54.00	0.00	0.02	0.02	0.01	50		0.00	0.00	456.580	443.920	12.660	14.450	0.000	
12	12	2	192.00	0.05	0.07	0.12	0.09	50		0.04	0.01	456.651	442.280	14.371	16.090	0.070	
13	13	12	97.00	0.00	0.03	0.03	0.02	50		0.01	0.00	456.651	440.920	15.731	17.450	0.000	
14	14	12	58.00	0.00	0.02	0.02	0.01	50		0.00	0.00	456.651	441.860	14.791	16.510	0.000	
15	15	6	93.00	0.06	0.03	0.10	0.08	50		0.03	0.01	456.592	443.500	13.092	14.870	0.050	

SISTEMA SANCAD

18/12/2006 às 14:17h

Rede de Água - Seccionamentos - Dados Finais

Cidade : P. A. VALE VERDE - TURBILHÃO 1 E 2

Nu	No Jus	No Mo	Compr m	Q Jus l/s	Q mar l/s	Q Mon l/s	Q fict l/s	DN1 mm	DN2 mm	Vel m/s	Hf mca	CP Juz mca	CT Juz m	PR Juz mca	PR Est mca	Perda Km mca	Obs
16	16	15	97.00	0.00	0.03	0.03	0.02	50		0.01	0.00	456.592	440.870	15.722	17.500	0.000	
17	17	15	79.00	0.00	0.03	0.03	0.01	50		0.01	0.00	456.592	441.010	15.582	17.360	0.000	
18	18	9	88.00	0.00	0.03	0.03	0.02	50		0.01	0.00	456.585	441.010	15.575	17.360	0.000	
19	19	1	45.00	1.08	0.02	1.09	1.08	50		0.46	0.24	456.557	443.180	13.377	15.190	5.380	
20	20	19	90.00	0.07	0.03	0.11	0.09	50		0.04	0.01	456.551	443.180	13.371	15.190	0.070	
21	21	20	100.00	0.04	0.04	0.07	0.06	50		0.02	0.00	456.548	442.090	14.458	16.280	0.030	
22	22	21	110.00	0.00	0.04	0.04	0.02	50		0.01	0.00	456.547	442.550	13.997	15.820	0.010	
23	23	19	56.00	0.95	0.02	0.97	0.96	50		0.41	0.24	456.316	443.400	12.916	14.970	4.300	
24	24	23	109.00	0.91	0.04	0.95	0.93	50		0.40	0.44	455.872	443.870	12.002	14.500	4.070	
25	25	24	108.00	0.06	0.04	0.10	0.08	50		0.03	0.01	455.866	443.670	12.196	14.700	0.060	
26	26	25	33.00	0.00	0.01	0.01	0.01	50		0.00	0.00	455.866	443.600	12.266	14.770	0.000	
27	27	25	138.00	0.00	0.05	0.05	0.02	50		0.01	0.00	455.865	442.550	13.315	15.820	0.010	
28	28	24	575.00	0.17	0.20	0.37	0.27	50		0.12	0.26	455.611	441.060	14.551	17.310	0.450	
29	29	28	108.00	0.00	0.04	0.04	0.02	50		0.01	0.00	455.610	441.500	14.110	16.870	0.010	
30	30	28	264.00	0.04	0.09	0.13	0.08	50		0.04	0.02	455.595	439.380	16.215	18.990	0.060	

SISTEMA SANCAD

18/12/2006 às 14:17h

Rede de Água - Seccionamentos - Dados Finais

Cidade : P. A. VALE VERDE - TURBILHÃO 1 E 2

Nu	No Jus	No Mo	Compr m	Q Jus l/s	Q mar l/s	Q Mon l/s	Q fict l/s	DN1 mm	DN2 mm	Vel m/s	Hf mca	CP Juz mca	CT Juz m	PR Juz mca	PR Est mca	Perda Km mca	Obs
31	31	30	108.00	0.00	0.04	0.04	0.02	50		0.01	0.00	455.594	439.890	15.704	18.480	0.010	
32	32	24	127.00	0.40	0.04	0.44	0.42	50		0.18	0.12	455.749	441.630	14.119	16.740	0.970	
33	33	32	581.00	0.19	0.21	0.40	0.29	50		0.12	0.30	455.448	441.500	13.948	16.870	0.520	
34	34	33	110.00	0.15	0.04	0.19	0.17	50		0.07	0.02	455.426	442.260	13.166	16.110	0.200	
35	35	34	53.00	0.00	0.02	0.02	0.01	50		0.00	0.00	455.426	442.510	12.916	15.860	0.000	
36	36	34	375.00	0.00	0.13	0.13	0.07	50		0.03	0.02	455.411	439.890	15.521	18.480	0.040	

finais.ret - Planilha gerada pelo Sistema SANCAD - Sanegraph Ltda. - Tel/fax: (031) 3337-0217