

SISTEMA SANCAD

01/02/2007 às 11:30h

Rede de Água - Seccionamentos - Dados Finais

Cidade : P. A. VALE VERDE - MANGAL 2

Nu	No Jus	No Mo	Compr m	Q Jus l/s	Q mar l/s	Q Mon l/s	Q fict l/s	DN1 mm	DN2 mm	Vel m/s	Hf mca	CP Juz mca	CT Juz m	PR Juz mca	PR Est mca	Perda Km mca	Obs
1	1	0	16.00	1.26	0.02	1.28	1.27	75		0.27	0.02	451.379	438.060	13.319	14.590	1.310	
2	2	1	151.00	1.08	0.18	1.26	1.17	50		0.50	0.94	450.440	437.230	13.210	15.420	6.220	
3	3	2	162.00	0.89	0.19	1.08	0.99	50		0.42	0.73	449.708	435.120	14.588	17.530	4.520	
4	4	3	107.00	0.76	0.13	0.89	0.82	50		0.35	0.35	449.359	436.950	12.409	15.700	3.260	
5	5	4	108.00	0.63	0.13	0.76	0.69	50		0.30	0.26	449.100	436.840	12.260	15.810	2.400	
6	6	5	107.00	0.50	0.13	0.63	0.56	50		0.24	0.18	448.923	438.450	10.473	14.200	1.650	
7	7	6	151.00	0.00	0.18	0.18	0.09	50		0.04	0.01	448.913	439.700	9.213	12.950	0.070	
8	8	6	265.00	0.00	0.32	0.32	0.16	50		0.07	0.05	448.875	438.290	10.585	14.360	0.180	

finais.ret - Planilha gerada pelo Sistema SANCAD - Sanegraph Ltda. - Tel/fax: (031) 3337-0217