

SISTEMA SANCAD

18/12/2006 às 16:26h

Rede de Água - Seccionamentos - Dados Finais

Cidade : P. A. VALE VERDE - VILA TURBILHÃO 3

Nu	No Jus	No Mo	Compr m	Q Jus l/s	Q mar l/s	Q Mon l/s	Q fict l/s	DN1 mm	DN2 mm	Vel m/s	Hf mca	CP Juz mca	CT Juz m	PR Juz mca	PR Est mca	Perda Km mca	Obs
1	1	0	20.00	1.61	0.01	1.62	1.61	75		0.34	0.04	460.240	447.031	13.209	14.499	2.050	
2	2	1	82.00	0.42	0.03	0.46	0.44	50		0.19	0.09	460.153	447.063	13.090	14.467	1.060	
3	3	2	128.00	0.32	0.05	0.37	0.34	50		0.15	0.09	460.065	445.166	14.899	16.364	0.690	
4	4	3	88.00	0.23	0.04	0.27	0.25	50		0.11	0.03	460.031	443.825	16.206	17.705	0.390	
5	5	4	143.00	0.11	0.06	0.17	0.14	50		0.06	0.02	460.009	447.764	12.245	13.766	0.150	
6	6	5	142.00	0.00	0.06	0.06	0.03	50		0.01	0.00	460.007	447.868	12.139	13.662	0.010	
7	7	5	127.00	0.00	0.05	0.05	0.03	50		0.01	0.00	460.008	447.431	12.577	14.099	0.010	
8	8	4	129.00	0.00	0.05	0.05	0.03	50		0.01	0.00	460.030	446.910	13.120	14.620	0.010	
9	9	3	118.00	0.00	0.05	0.05	0.03	50		0.01	0.00	460.064	446.666	13.398	14.864	0.010	
10	10	2	121.00	0.00	0.05	0.05	0.03	50		0.01	0.00	460.152	446.564	13.588	14.966	0.010	
11	11	1	120.00	1.10	0.05	1.15	1.13	50		0.48	0.69	459.546	446.058	13.488	15.472	5.780	
12	12	11	90.00	1.06	0.04	1.10	1.08	50		0.46	0.48	459.062	446.564	12.498	14.966	5.380	
13	13	12	130.00	0.71	0.06	0.77	0.74	50		0.32	0.35	458.710	446.666	12.044	14.864	2.710	
14	14	13	100.00	0.48	0.04	0.52	0.50	50		0.21	0.13	458.577	446.910	11.667	14.620	1.330	
15	15	14	128.00	0.21	0.05	0.26	0.23	50		0.10	0.05	458.532	447.431	11.101	14.099	0.350	

SISTEMA SANCAD

18/12/2006 às 16:26h

Rede de Água - Seccionamentos - Dados Finais

Cidade : P. A. VALE VERDE - VILA TURBILHÃO 3

Nu	No Jus	No Mo	Compr m	Q Jus l/s	Q mar l/s	Q Mon l/s	Q fict l/s	DN1 mm	DN2 mm	Vel m/s	Hf mca	CP Juz mca	CT Juz m	PR Juz mca	PR Est mca	Perda Km mca	Obs
16	16	15	130.00	0.15	0.06	0.21	0.18	50		0.08	0.03	458.503	446.726	11.777	14.804	0.220	
17	17	16	75.00	0.00	0.03	0.03	0.02	50		0.01	0.00	458.503	446.748	11.755	14.782	0.000	
18	18	16	130.00	0.06	0.06	0.12	0.09	50		0.04	0.01	458.494	445.234	13.260	16.296	0.070	
19	19	18	101.00	0.00	0.04	0.04	0.02	50		0.01	0.00	458.493	443.926	14.567	17.604	0.010	
20	20	18	51.00	0.00	0.02	0.02	0.01	50		0.00	0.00	458.494	445.773	12.721	15.757	0.000	
21	21	12	129.00	0.24	0.05	0.29	0.27	50		0.11	0.06	459.005	445.266	13.739	16.264	0.440	
22	22	21	96.00	0.00	0.04	0.04	0.02	50		0.01	0.00	459.004	444.350	14.654	17.180	0.010	
23	23	21	127.00	0.00	0.05	0.05	0.03	50		0.01	0.00	459.004	445.936	13.068	15.594	0.010	
24	24	21	132.00	0.09	0.06	0.15	0.12	50		0.05	0.01	458.991	443.882	15.109	17.648	0.110	
25	25	24	126.00	0.00	0.05	0.05	0.03	50		0.01	0.00	458.990	444.990	14.000	16.540	0.010	
26	26	24	85.00	0.00	0.04	0.04	0.02	50		0.01	0.00	458.991	443.102	15.889	18.428	0.000	
27	27	13	129.00	0.14	0.05	0.19	0.17	50		0.07	0.03	458.685	445.936	12.749	15.594	0.190	
28	28	27	100.00	0.00	0.04	0.04	0.02	50		0.01	0.00	458.684	446.250	12.434	15.280	0.010	
29	29	27	131.00	0.04	0.06	0.10	0.07	50		0.03	0.01	458.679	444.990	13.689	16.540	0.050	
30	30	29	100.00	0.00	0.04	0.04	0.02	50		0.01	0.00	458.678	445.098	13.580	16.432	0.010	

SISTEMA SANCAD

18/12/2006 às 16:26h

Rede de Água - Seccionamentos - Dados Finais

Cidade : P. A. VALE VERDE - VILA TURBILHÃO 3

Nu	No Jus	No Mo	Compr m	Q Jus l/s	Q mar l/s	Q Mon l/s	Q fict l/s	DN1 mm	DN2 mm	Vel m/s	Hf mca	CP Juz mca	CT Juz m	PR Juz mca	PR Est mca	Perda Km mca	Obs
31	31	14	127.00	0.16	0.05	0.22	0.19	50		0.08	0.03	458.546	446.250	12.296	15.280	0.240	
32	32	31	127.00	0.00	0.05	0.05	0.03	50		0.01	0.00	458.545	446.726	11.819	14.804	0.010	
33	33	31	129.00	0.05	0.05	0.11	0.08	50		0.03	0.01	458.539	445.098	13.441	16.432	0.050	
34	34	33	128.00	0.00	0.05	0.05	0.03	50		0.01	0.00	458.538	445.234	13.304	16.296	0.010	

finais.ret - Planilha gerada pelo Sistema SANCAD - Sanegraph Ltda. - Tel/fax: (031) 3337-0217